



**RELIABLE - R15 SERIES - INSULATED JUMPER SETS**

Reliable Equipment offers a full range of preassembled Jumper Cables for bypassing work areas where equipment is under repair, the line is being upgraded, and for making temporary or other emergency repairs. Sets can be assembled to meet any of your conductor, AMP, line range, and cable length requirements from 1/0 to 4/0 in 15kV sets.

**Jumper Cable - 5/15 kV Dual Rated**

| Part    | Size | AMP | Approx. Cable O.D. |
|---------|------|-----|--------------------|
| R15-1/0 | 1/0  | 260 | 1,000              |
| R15-2/0 | 2/0  | 300 | 1,055              |
| R15-4/0 | 4/0  | 400 | 1,165              |

**Ferrules (unshrouded) - (sold in pairs)**

| Part | Cable | Stud       | AMP |
|------|-------|------------|-----|
| 2023 | 1/0   | 5/8"-11 NC | 400 |
| 2024 | 2/0   | 5/8"-11 NC | 400 |
| 2025 | 4/0   | 5/8"-11 NC | 400 |

**Jumper Clamps - (sold in pairs)**

| Part | Range              | AMP | Head Style    |
|------|--------------------|-----|---------------|
| 2115 | #6 SOL to 954 ACSR | 400 | Clear Plastic |
| 2270 | #6 SOL to 954 ACSR | 400 | H/D Salcor    |

**How to order Jumper Sets**

Specify cable size, length, and clamp style

**Ex: R15-1/0 x 12-2270**

Other kV size cables and clamps styles available upon request.

Contact Reliable for more information.

**SALCOR<sup>®</sup> INSULATED CLAMPS**

"Rubber covered" hot bypass jumper clamps. Metal components and conventional electrical/mechanical design.

Thermosetting Elastomer Handle, 11.5" O.A.L. with 1.5" I.D., 7.5" below Hand Guard.

| Part | Main Line Range                                   | Description                          | Max. Amps |
|------|---|--------------------------------------|-----------|
| 2260 | 477 MCM, (30x7) ACSR to #6 Sol., .883"-.162" Dia. | Clamps, Insulated Jumper (Pair) Only | 400       |
| 2270 | 954 MCM, (36x1) ACSR to #6 Sol., 1.14"-.162" Dia. | Clamps, Insulated Jumper (Pair) Only | 400       |

**TO ORDER CALL: 800-966-3530 OR FAX: 215-357-9193**